green connected & THRIVING
MINISTRY OF BUILDINGS, UTILITIES, INFRASTRUCTURE, LABOUR & TRANSPORTATION

P O BOX 344, BRADES, MONTSERRAT, W I
◈ Tel: (664) 491-2521/2522 ◈ Fax: (664) 491-6659 ◈ E-mail: mcw@gov.ms

27th October 2026

Dear Sir/Madam,

ADDENDUM No. 1– Bill of Quantities

Re: Request for Quotation - Structural Concrete Repairs to Brades Primary School

Description:

Bidders are asked to take note of the attached Bill of Quantities (Annex I) which was omitted in error during publication.

All queries and clarification relating to this quotation should be sent to Mr. Rawlson Patterson, Director, PWD at pattersonr@gov.ms and copied to daleyam@gov.ms.

Best Regards

Rawlson Patterson
Director
Public Works Department

Price Bill of Quantities

[Complete this form and include it as part of your tender. Ensure that it is signed by an authorised person. All items of works in the Bill of Quantities must be filled out by Tenderer)

Name of tenderer	
Procurement reference number	BUILTE/INFRA/2026/27-11
Currency of tender	Eastern Caribbean Dollars (XCD)

Price Bill of Quantities (Admeasurement Contract)

Quotation for Relocation of Airport Perimeter Fencing to Enclose the Airport Tower

Item	Description	Units	Quantity	Rate	Total
A	**Preliminaries**				
a.1	Contractor's preliminaries, mobilisation and insurance cost. The contractor shall be responsible for the safety of the employees during the construction phase. Further, it is the contractor's responsibilty to make contact with all utilities prior to commencement of works and where necessary shall make provision for re-routing any utilities which may interfere with the works.	Item	1.00		
B	**Excavation Works**				
b.1	Excavate for placement of concrete for securing metal fence post in compliance with drawing details on Sheet No. 01. Post should be spaced at 10ft (3.05m) intervals and holes measure 12"wide x 12"wide x 30" deep.	Item	1.00		
b.2	Carefully remove, relocate, and reinstall the existing fence posts at the new location without causing damage	Item	1.00		
b.3	Provide labour and materials to backfill and properly compact all holes remaining from the removal of the existing fence posts at the original location	Item	1.00		
C	**Concrete Works**				
c.1	The Contractor shall supply and place 3,000 psi concrete to secure the fence foundations. The concrete footings shall be finished below finished grade to ensure they are hidden from public view, maintaining a uniform appearance consistent with the existing airport perimeter fencing.	m^3	1.10		
D	**Metal Works**				
d.1	The Contractor shall execute the following fence modifications: **Removal & Reuse**: Extract existing airport perimeter fence poles and reuse them to extend the perimeter fencing around the Airport Tower enclosure. **Spacing & Height**: Install new galvanized steel poles at 3.05 m (10 ft) intervals, maintaining a height of 2.44 m (8 ft) above finished ground level. **Finishes**: Coat all fence poles with a dark brown anti-corrosive paint.	No.	15.00		
d.2	The Contractor shall carefully dismantle and salvage the existing fencing for relocation around the Airport Tower. Following the necessary cutting of the existing fabric, the Contractor shall ensure the relocated fencing is securely and seamlessly tied back into the remaining perimeter structure.	m	33.00		
E	**Temporary Hoarding**				
e.1	Supply, erect, maintain and remove temporary closed-board security hoarding min 2 m high, installed parallel and immediately behind existing fence to be removed for relocation, to prevent public access to airside during fence relocation, including frame, bracing to resist wind/jet blast, anti-climb finish, sealed joints, security signage, daily inspections and maintenance for full duration of works and final removal - complete in accordance with Airport Security requirements.	m	33.00		
F	**Contingency**				
f.1	Planned contingency for unforeseen works within parameters of the scope of work.	P.Sum			$ 1,500.00
	Nb: Employer shall be resposible for the provision of the fencing poles and fencing				
	Nb: Contractor shall be responsible for providing its own power and transportation of water to site.				
	Total to Form Quotation				

Priced Bill of Quantities

Signature	
Name of authorised signatory	
Position of authorised signatory	
Name of tenderer	
Date signed	

Priced Bill of Quantities